

令和4年度 防災・安全交付金事業 市道西条33号線舗装修繕工事（繰越明許）

数量計算書

市道西条33号線 中野市大字西条

数量総括表

[illegible]

数量計算書

測点名	測 点	距 離	舗装面積			舗装切断			区画線								
			幅	平 均	面 積	左	中心・端部	右	外側左	ドット破線	中心実線	中心破線	ドット破線	外側右	停止・横断歩道	マーク15cm	備考
BP-7.9	-7.90		0.00				10.7										
BP	0.00	7.90	6.80	3.40	26.9		708.0				35.7			7.9	2.9		
NO.1	20.00	20.00	6.90	6.85	137.0	16.3			20.0					20.0			
NO.2	40.00	20.00	6.30	6.60	132.0				20.0			105.0		20.0			
NO.3	60.00	20.00	5.90	6.10	122.0				20.0					20.0			
NO.4	80.00	20.00	6.00	5.95	119.0			7.7	20.0					12.3		5.6	T字×1
NO.5	100.00	20.00	6.20	6.10	122.0	10.1			20.0					20.0			
NO.6	120.00	20.00	6.20	6.20	124.0				20.0					20.0			
NO.7	140.00	20.00	6.30	6.25	125.0				20.0					20.0			
NO.8	160.00	20.00	6.20	6.25	125.0				20.0					20.0			
NO.9	180.00	20.00	6.30	6.25	125.0				20.0					20.0			
NO.10	200.00	20.00	6.10	6.20	124.0				20.0					20.0			
NO.11	220.00	20.00	6.70	6.40	128.0				20.0					20.0		54.0	Λ×4
NO.12	240.00	20.00	7.20	6.95	139.0				20.0					20.0		33.0	ﾀﾞｲﾔ×2
NO.13	260.00	20.00	7.50	7.35	147.0				20.0					20.0	2.9		
NO.14	280.00	20.00	7.50	7.50	150.0				20.0		33.3			20.0	24.0		
NO.15	300.00	20.00	7.40	7.45	149.0	15.7		15.5	7.7	5.0	30.0		7.0	5.7	2.9	11.2	T字×2
NO.16	320.00	20.00	7.20	7.30	146.0				20.0			80.0		20.0		33.0	ﾀﾞｲﾔ×2
NO.17	340.00	20.00	7.20	7.20	144.0				20.0					20.0		54.0	Λ×4
NO.18	360.00	20.00	7.20	7.20	144.0				20.0					20.0			
NO.19	380.00	20.00	7.20	7.20	144.0				20.0					20.0			
NO.20	400.00	20.00	7.20	7.20	144.0				20.0					20.0			
NO.21	420.00	20.00	7.20	7.20	144.0				20.0					20.0			
NO.22	440.00	20.00	7.20	7.20	144.0				20.0					20.0			
NO.23	460.00	20.00	7.20	7.20	144.0				20.0					20.0		54.0	Λ×4
NO.24	480.00	20.00	7.20	7.20	144.0				20.0					20.0			
NO.25	500.00	20.00	7.20	7.20	144.0	15.8		16.0	8.9	7.0	40.2		8.0	8.6		11.2	T字×2
NO.26	520.00	20.00	7.20	7.20	144.0				20.0			65.0		20.0			
NO.27	540.00	20.00	7.20	7.20	144.0				20.0					20.0		54.0	Λ×4
NO.28	560.00	20.00	7.20	7.20	144.0				20.0					20.0			
NO.29	580.00	20.00	7.20	7.20	144.0				20.0					20.0			
NO.30	600.00	20.00	7.20	7.20	144.0				20.0					20.0			
NO.30+6.9	606.90	6.90	7.20	7.20	49.7				6.9					6.9			
NO.30+6.9	606.90	0.00	6.90	7.05	0.0				0.0					0.0			
NO.31	620.00	13.10	7.00	6.95	91.0				13.1					13.1			
NO.32	640.00	20.00	7.10	7.05	141.0				20.0					20.0			
NO.33	660.00	20.00	7.10	7.10	142.0				20.0					20.0			
NO.34	680.00	20.00	7.00	7.05	141.0				20.0					20.0	2.9		
NO.35	700.00	20.00	6.80	6.90	138.0				20.0					20.0			
NO.35+4.0	704.00	4.00	6.80	6.80	27.2		6.8		4.0		36.6			4.0			
控除 NO.20付近横断側溝					-3.0												
合計		711.90			4,883.8	822.6			680.6	12.0	175.8	250.0	15.0	678.5	35.6	310.0	

区画線工の種類が1つのみの場合

リスト 番号	名称・規格・仕様	① 設計数量 (m)	② 日当たり標 準作業量 (m)	①／②	設計計上数量(m)		
					全ての費用	機・労のみ	材料費のみ

区画線工の種類が複数ある場合

リスト 番号	名称・規格・仕様	① 設計数量 (m)	② 日当たり標 準作業量 (m)	①／②	α	設計計上数量(m)		
						全ての費用	機・労のみ	材料費のみ
1	ペイント式 加熱式 溶剤型 実線 15cm 供用区間	1530	3,000	0.51	—	1,530	—	—
3	ペイント式 加熱式 溶剤型 破線 15cm 供用区間	280	2,500	0.112	—	280	—	—
69	溶融式 ゼブラ 45cm 供用区間	36	450	0.08	—	36	—	—
73	溶融式 矢印・記号・文字(15cm換算) 供用区間	310	400	0.775	—	310	—	—
計				1.477				

区画線消去(ウォータージェット式)を積算に用いる場合

リスト 番号	名称・規格・仕様	① 設計数量 (m)	② 日当たり標 準作業量 (m)	①／②	設計計上数量 (m)